BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer, Dasarahalli Division
Scheule-B

NAME OF THE WORK: Improvements to roads and drains at Raghavendra Layout main and cross roads in Ward No 12 in Shettyhalli Sub division

Sl. No	Description of work	Unit	Qty	Rates quoted by contractor Sri R.Shivaram	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 1.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 (Page No.-142 I.No-19.1 of KPWD S.R 2016-17)	Cum	1362	184.75	Rupees One Hundred Eighty Four and Seventy Five Paise Only
2	KSRB 4-1.3 : Providing and laying in position plain cement concrete cum of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. (Page No. 12, It No. 4.3 of KPWD S.R 2016-17)	Cum	201.06	5099.17	Rupees Five Thousand Ninety Nine and Seventeen Paise Only
3	KSRB 4-6.4: Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specificaitons. Specification No. KBS 4.6.2.(Page No.-15 I.No-4.31 of KPWD S.R 2016-17)	Sqm	4014	306.98	Rupees Three Hundred Six and Ninety Seven Paise Only

Signatureof the Contractor

Executive Engineer
Dasarahalli Division
BBMP

Scanned with CamScanner

4	SRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications and as per directions of the Engineer-in-charge. Specification No. KBS 4.6.3(Item no: 4.46.2, Page no: 17 of KPWD S.R 2016-17).f machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2	Tonne	29.26	63498.20	Rupees Sixty Three Thousan Four Hundred Ninety Eight an Nineteen Paise Only
5	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mix concrete(RMC) for RCC works laid in 15 cms thick layers and well conpacted vibrating, curing, finishing with necessary cement mortar, with all lead and lifts etc., complete (exlusive of cost of steel and fabrication charges) Ready mix concrete M-20 for raft foundation, coulmn and footing, main ans secondary beams.(Page No.-18 I.No-4.48 of KPWD S.R 2016-17)	Cum	476.34	6159.45	Rupees Six Thousand One Hundred Fifty Nine and Forty Five Paise Only
6	Providing and laying pre-cast drain cover slab of 100mm thickness in CM1:3 including cost of all materials,labour,curing, transportation, loading, unloading etc.,as per doiirections of the Enineer-in-charge. {Data Rate sheet enclosed}	Sqm	1151.2	1851.27	Rupees One Thousand Eight Hundred Fifty One and Twenty Seven Paise Only
7	Providing and laying Pre Cast Drain Cover slabs of 250mm thickness including cost of all materials, labour, curing, transportation,loading, unloading etc.,complete as per the direction of Engineer - In-Charge. (Data Rate enclosed)	Sqm	108	4169.07	Rupees Four Thousand One Hundred Sixty Nine and Seven Paise Only

Signatureof the Contractor

Executive Engineer
Dasarahalli Division
BBMP

Scanned with CamScanner